



**NOTES :**

1. CONCRETE SHALL BE CLASS "A"
2. FLOOR OF STRUCTURE SHALL BE GIVEN A STEEL TROWEL FINISH.
3. TOP OF BOX TO HAVE SIDEWALK FINISH.
4. ANCHORS SHALL BE SYMMETRICALLY SPACED AND NOT TO EXCEED 4' BETWEEN CENTERS, AND BE PLACED 4 1/2" FROM EACH END OF THE STEEL ANGLE, A MINIMUM OF 3 ANCHORS IS REQUIRED.

SAN BERNARDINO COUNTY TRANS. DEPT.		OUTLET STRUCTURE	210A
120 8-89	KEN A. MILLER Director of Transportation		