April 10, 2018

Duke Realty 200 Spectrum Center Drive, Suite 1600 Irvine, California 92618



Attention: Mr. Adam Schmid

Development Services Manager

Project No.: **17G218-2**

Subject: Results of Infiltration Testing

Proposed Commercial/Industrial Building NWC Alabama Street and Palmetto Avenue

San Bernardino County, California

Reference: Geotechnical Investigation, Proposed Commercial/Industrial Building, NWC

Alabama Street and Palmetto Avenue, San Bernardino, California, prepared by Southern California Geotechnical, Inc. (SCG) for Duke Realty, SCG Project No.

17G218-1, dated December 15, 2017.

Dear Mr. Schmid:

In accordance with your request, we have conducted infiltration testing at the subject site. We are pleased to present this report summarizing the results of the infiltration testing and our design recommendations.

Scope of Services

The scope of services performed for this project was in general accordance with our Change Order 17G218-CO, dated March 9, 2018. The scope of services included site reconnaissance, subsurface exploration, field testing, and engineering analysis to determine the infiltration rates of the onsite soils. The infiltration testing was performed in general accordance with ASTM Test Method D-3385-03, Standard Test Method for Infiltration Rate of Soils in Field Using Double Ring Infiltrometer.

Site and Project Description

The subject site is located at the northwest corner of Palmetto Avenue and Alabama Street in an unincorporated portion of San Bernardino County near Redlands, California. The site is bounded to the north by a vacant lot, to the west by vacant land and a commercial/industrial building, to the south by Palmetto Avenue, and to the east by Alabama Street. The general location of the site is illustrated on the Site Location Map, included as Plate 1 of this report.

The site consists of several parcels, which total 56± acres in size. The majority of the site is vacant and undeveloped. The ground surface cover generally consists of exposed soil with moderate to dense native grass and weed growth, with several large trees located throughout the site. The northern region of the western parcel is developed with a small farm house. The majority of this parcel is currently being utilized for agricultural purposes. Ground surface cover

22885 Savi Ranch Parkway ▼ Suite E ▼ Yorba Linda ▼ California ▼ 92887 voice: (714) 685-1115 ▼ fax: (714) 685-1118 ▼ www.socalgeo.com

in this area and surrounding the farm house consists of exposed soil with moderate to dense native grass, weed growth, and planted crops. Multiple small to large trees are located throughout this parcel. A natural drainage course is present in the northeast corner of the overall site that is 20± feet lower in elevation than the adjacent site grades.

Detailed topographic information was provided by Albert A. Webb Associates (Webb). The site topography generally ranges from $1199\pm$ feet mean sea level (msl) in northwestern corner of the site to $1226\pm$ feet msl in the southeastern corner of the site. However, the bottom of the existing drainage course, located at the northeast corner of the site is at an elevation of $1186\pm$ feet msl. With the exception of the drainage course, the site topography slopes gently downward to the northwest at a gradient of $1\pm$ percent. In the northeast corner of the site, the site grades slope downward into the drainage course at an approximate inclination of $12\pm$ 1 (horizontal to vertical).

Proposed Development

A conceptual site plan, prepared by Albert A. Webb Associates (Webb), was provided to our office by the client. The plan indicates that the subject site will be developed with one (1) new commercial/industrial building. The proposed building will be 1,192,671± ft² in size, located in the central area of the site. The building will be constructed in a cross-dock configuration with loading docks along both the east and west sides of the building. The building will be surrounded by asphaltic concrete pavements for automobile parking and drive lanes and Portland cement concrete pavements for the loading dock areas. Several landscape planters and concrete flatwork are expected to be included throughout the site. The site plan does not indicate any proposed development within the existing drainage course located at the northeast corner of the site.

We understand that the proposed development will include on-site infiltration to dispose of storm water. Based on an Infiltration Test Exhibit, prepared by Webb, the project civil engineer, the proposed infiltration system will consist of two (2) detention/infiltration basins. The basins will be located in the northwest corner and in the southwest region of the site. The bottoms of the basins will extend to depths ranging from 4 to $7\pm$ feet below the existing site grades.

Previous Study

Southern California Geotechnical, Inc. (SCG) previously performed a geotechnical investigation at the subject site, referenced above. As a part of this study, ten (10) borings were advanced to depths of 5 to $30\pm$ feet below existing site grades. Artificial fill soils were encountered at the ground surface at one of the boring locations, extending to a depth of $6\frac{1}{2}\pm$ feet below the existing site grades. The fill soils generally consisted of very loose to loose fine to medium sands with varying amounts of coarse sand, silt, and fine gravel content. Native alluvial soils were encountered beneath the fill soils and at the ground surface at the remaining boring locations. The near-surface alluvium possessed a disturbed appearance and was identified as disturbed alluvium. These soils generally consisted of very loose to loose silty fine sands to fine sandy silts with trace amounts of fine root fibers. Undisturbed native alluvial soils were encountered at all of the boring locations, beneath the disturbed alluvium or fill soils, extending to the maximum depth explored of $30\pm$ feet below existing site grades. The native alluvium generally consisted of very loose to medium dense silty fine sands, fine sandy silts, and fine to medium sands. Free



water was not encountered during the drilling of any of the borings. Based on the lack of any water within the borings and the moisture contents of the recovered soil samples, the static groundwater is considered to have existed at a depth in excess of 30± feet at the time of the subsurface exploration. The approximate locations of the ten (10) borings from the previous study are indicated on the Infiltration Test Location Plan, included as Plate 2 of this report.

Subsurface Exploration

Scope of Exploration

The subsurface exploration consisted of five (5) backhoe excavated trenches, extending to depths of 4 to 7± feet below existing site grades. The trenches were logged during excavation by a member of our staff. The approximate locations of the infiltration trenches (identified as I-1 through I-5) are indicated on the Infiltration Test Location Plan, enclosed as Plate 2 of this report.

Geotechnical Conditions

Native alluvium was encountered at the ground surface at all of the infiltration trench locations, extending to at least the maximum depth explored of 7± feet below existing site grades. The alluvial soils generally consist of very loose to medium dense silty fine sands and fine sandy silts with varying amounts of medium to coarse sands. The Trench Logs, which illustrate the conditions encountered at the infiltration trench locations, are included with this report.

Groundwater

As part of our research, we reviewed available groundwater data in order to determine the historic high groundwater level for the site. Recent water level data was obtained from the California Department of Water Resources website, http://www.water.ca.gov/waterdatalibrary/. The nearest monitoring well is located in the southeastern region of the subject site. Water level readings within this monitoring well indicates high groundwater levels of 130± feet (April 2005) below the ground surface.

Infiltration Testing

We understand that the results of the testing will be used to prepare a preliminary design for the storm water infiltration system that will be used at the subject site. As previously mentioned, the infiltration testing was performed in general accordance with ASTM Test Method D-3385-03, Standard Test Method for Infiltration Rate of Soils in Field Using Double Ring Infiltrometer.

Two stainless steel infiltration rings were used for the infiltration testing. The outer infiltration ring is 2 feet in diameter and 20 inches in height. The inner infiltration ring is 1 foot in diameter and 20 inches in height. At the test locations, the outer ring was driven $3\pm$ inches into the soil at the base of each trench. The inner ring was centered inside the outer ring and subsequently driven $3\pm$ inches into the soil at the base of the trench. The rings were driven into the soil using a ten-pound sledge hammer. The soil surrounding the wall of the infiltration rings was only slightly disturbed during the driving process.



<u>Infiltration Testing Procedure</u>

Infiltration testing was performed at all five (5) of the test locations. The infiltration testing consisted of filling the inner ring and the annular space (the space between the inner and outer rings) with water, approximately 3 to 4 inches above the soil. To prevent the flow of water from one ring to the other, the water level in both the inner ring and the annular space between the rings was maintained using constant-head float valves. The volume of water that was added to maintain a constant head in the inner ring and the annular space during each time interval was determined and recorded. A cap was placed over the rings to minimize the evaporation of water during the tests.

The schedule for readings was determined based on the observed soil type at the base of each backhoe-excavated trench. Based on the existing soils at each infiltration test location, the volumetric measurements were made at increments of 10 minutes. The water volume measurements are presented on the spreadsheets enclosed with this report. The infiltration rates for each of the timed intervals are also tabulated on these spreadsheets.

The infiltration rates for the infiltration tests are calculated in centimeters per hour and then converted to inches per hour. The rates are summarized below:

Infiltration Test No.	<u>Test</u> <u>Elevation</u> (msl)	Soil Description	<u>Infiltration</u> <u>Rate</u> (inches/hour)
I-1	1198.5	Silty fine Sand	3.6
I-2	1198	Silty fine Sand, trace medium Sand	3.1
I-3	1198.5	Silty fine Sand	3.2
I-4	1195	Silty fine Sand	3.7
I-5	1197	Silty fine Sand, little medium Sand	2.5

Laboratory Testing

In-situ Moisture Content

The moisture contents for selected soil samples collected from the trenches were determined in accordance with ASTM D-2216 and are expressed as a percentage of the dry weight. These test results are presented on the Trench Logs.

Grain Size Analysis

The grain size distribution of selected soils collected from the base of each infiltration test trench has been determined using a range of wire mesh screens. These tests were performed in general accordance with ASTM D-422 and/or ASTM D-1140. The weight of the portion of the



sample retained on each screen is recorded and the percentage finer or coarser of the total weight is calculated. The results of these tests are presented at the end of this report.

Design Recommendations

A total of five (5) infiltration tests were performed at the subject site. As noted above, the calculated infiltration rates at the infiltration test locations range from 2.5 to 3.7 inches per hour. The primary factors affecting the infiltration rates are the varying relative densities and silt content of the encountered soils, which vary at different depths and locations at the subject site.

Based on the infiltration test results, we recommend a design infiltration rate of 3 inches per hour be used for the proposed detention/infiltration basin located in the northwest corner of the site and a design rate of 2.5 inches per hour for the basin located in the southwest region of the subject site.

The design of the proposed storm water infiltration systems should be performed by the project civil engineer, in accordance with the County of San Bernardino guidelines. However, it is recommended that the system be constructed so as to facilitate removal of silt and clay, or other deleterious materials from any water that may enter the system. The presence of such materials would decrease the effective infiltration rate. It is recommended that the project civil engineer apply an appropriate factor of safety. The infiltration rates recommended above is based on the assumption that only clean water will be introduced to the subsurface profile. Any fines, debris, or organic materials could significantly impact the infiltration rates. It should be noted that the recommended infiltration rates are based on infiltration testing at five (5) discrete locations and the overall infiltration rates of the storm water infiltration systems could vary considerably.

Infiltration versus Permeability

Infiltration rates are based on unsaturated flow. As water is introduced into soils by infiltration, the soils become saturated and the wetting front advances from the unsaturated zone to the saturated zone. Once the soils become saturated, infiltration rates become zero, and water can only move through soils by hydraulic conductivity at a rate determined by pressure head and soil permeability. The infiltration rates presented herein were determined in accordance with the ASTM Test Method D-3385-03 standard and are considered valid for the time and place of the actual test. Changes in soil moisture content will affect these infiltration rates. Infiltration rates should be expected to decrease until the soils become saturated. Soil permeability values will then govern groundwater movement. Permeability values may be on the order of 10 to 20 times less than infiltration rates. The system designer should incorporate adequate factors of safety and allow for overflow design into appropriate traditional storm drain systems, which would transport storm water off-site.

Location of Infiltration Systems

The use of on-site storm water infiltration systems carries a risk of creating adverse geotechnical conditions. Increasing the moisture content of the soil can cause the soil to lose internal shear strength and increase its compressibility, resulting in a change in the designed engineering properties. Overlying structures and pavements in the infiltration areas could potentially be



damaged due to saturation of subgrade soils. The proposed infiltration systems for this site should be located at least 25 feet away from any structures, including retaining walls. Even with this provision of locating the infiltration system at least 25 feet from the building, it is possible that infiltrating water into the subsurface soils could have an adverse effect on the proposed or existing structures. It should also be noted that utility trenches which happen to collect storm water can also serve as conduits to transmit storm water toward the structure, depending on the slope of the utility trench. Therefore, consideration should also be given to the proposed locations of underground utilities which may pass near the proposed infiltration system.

General Comments

This report has been prepared as an instrument of service for use by the client in order to aid in the evaluation of this property and to assist the architects and engineers in the design and preparation of the project plans and specifications. This report may be provided to the contractor(s) and other design consultants to disclose information relative to the project. However, this report is not intended to be utilized as a specification in and of itself, without appropriate interpretation by the project architect, structural engineer, and/or civil engineer. The design of the infiltration system is the responsibility of the civil engineer. The role of the geotechnical engineer is limited to determination of infiltration rate only. By using the design infiltration rates contained herein, the civil engineer agrees to indemnify, defend, and hold harmless the geotechnical engineer for all aspects of the design and performance of the infiltration system. The reproduction and distribution of this report must be authorized by the client and Southern California Geotechnical, Inc. Furthermore, any reliance on this report by an unauthorized third party is at such party's sole risk, and we accept no responsibility for damage or loss which may occur.

The analysis of this site was based on a subsurface profile interpolated from limited discrete soil samples. While the materials encountered in the project area are considered to be representative of the total area, some variations should be expected between trench locations and testing depths. If the conditions encountered during construction vary significantly from those detailed herein, we should be contacted immediately to determine if the conditions alter the recommendations contained herein.

This report has been based on assumed or provided characteristics of the proposed development. It is recommended that the owner, client, architect, structural engineer, and civil engineer carefully review these assumptions to ensure that they are consistent with the characteristics of the proposed development. If discrepancies exist, they should be brought to our attention to verify that they do not affect the conclusions and recommendations contained herein. We also recommend that the project plans and specifications be submitted to our office for review to verify that our recommendations have been correctly interpreted. The analysis, conclusions, and recommendations contained within this report have been promulgated in accordance with generally accepted professional geotechnical engineering practice. No other warranty is implied or expressed.



Closure

We sincerely appreciate the opportunity to be of service on this project. We look forward to providing additional consulting services during the course of the project. If we may be of further assistance in any manner, please contact our office.

Respectfully Submitted,

SOUTHERN CALIFORNIA GEOTECHNICAL, INC.

Scott McCann Staff Scientist

Gregory K. Mitchell, GE 2364

Principal Engineer

Distribution: (1) Addressee

Enclosures: Plate 1 - Site Location Map


Plate 2 - Infiltration Test Location Plan

Trench Logs (5 pages)

Infiltration Test Results Spreadsheets (5 pages)

Grain Size Distribution Graphs (5 pages)





SOURCE: SAN BERNARDINO COUNTY THOMAS GUIDE, 2013



SITE LOCATION MAP


PROPOSED COMMERCIAL/INDUSTRIAL BUILDING SAN BERNARDINO COUNTY, CALIFORNIA

SCALE: 1" = 2400'

DRAWN: SM CHKD: RGT

SCG PROJECT 17G218-2 PLATE 1





TRENCH NO. **I-1**

JOB NO.: 17G218-2

EQUIPMENT USED: Backhoe

LOGGED BY: Scott McCann

WATER DEPTH: Dry

PROJECT: Proposed Commercial/Industrial Building

SEEPAGE DEPTH: Dry

LOCATION: San Bernardino County, CA

ORIENTATION: S 2 E

DATE: 3-20-2018

TOP OF TRENCH ELEVATION: 1202.5 feet msl

READINGS TAKEN: At Completion

DATE	ATE. 3-20-2010 TOP OF TREINGH ELEVATION. 1202.3 leet his						
DEPTH	SAMPLE	DRY DENSITY (PCF)	MOISTURE (%)	EARTH MATERIALS DESCRIPTION	GRAPHIC REPRESENTATION S2E SCALE: 1" = 5'		
_				A: ALLUVIUM: Gray Brown Silty fine Sand, little medium Sand, trace coarse Sand, abundant fine root fibers, loose - moist			
			4	B: ALLUVIUM: Light Gray Brown Silty fine Sand, trace fine root fibers, loose to medium dense - damp			
	b		4	Trench Terminated @ 4 feet			
5 —				Bottom of Trench Elevation: 1198.5 feet msl			
_							
_							
10 —							
_							
-							
15 —							

KEY TO SAMPLE TYPES: B - BULK SAMPLE (DISTURBED) R - RING SAMPLE 2-1/2" DIAMETER (RELATIVELY UNDISTURBED)

TRENCH NO. I-2

JOB NO.: 17G218-2 EQUIPMENT USED: Backhoe WATER DEPTH: Dry

PROJECT: Proposed Commercial/Industrial Building

LOGGED BY: Scott McCann

SEEPAGE DEPTH: Dry

LOCATION: San Bernardino County, CA ORIENTATION: N 4 E

DATE: 3-20-2018 TOP OF TRENCH FLEVATION: 1204 feet msl READINGS TAKEN: At Completion

DAT	E: 3-20)-2018	8 TOP OF TRENCH ELEVATION: 1204 feet msl READINGS TAKEN: At Completion								
DEPTH	SAMPLE	DRY DENSITY (PCF)	MOISTURE (%)	EARTH MATERIALS DESCRIPTION	N 2		C REPRESEI		SCALE: 1" = 5'		
5 — 10 — 15 — — 15 — — — — — — — — — — — — — — — — — — —	b		5	A: ALLUVIUM: Gray Brown Silty fine Sand, little medium Sand, trace coarse Sand, abundant fine root fibers, loose - moist B: ALLUVIUM: Light Gray Brown Silty fine Sand, trace fine root fibers, loose to medium dense - damp C: ALLUVIUM: Light Gray Brown Silty fine Sand, trace medium Sand, medium dense - damp Trench Terminated @ 6 feet Bottom of Trench Elevation: 1198 feet msl				B			

KEY TO SAMPLE TYPES: B - BULK SAMPLE (DISTURBED) R - RING SAMPLE 2-1/2" DIAMETER (RELATIVELY UNDISTURBED)

TRENCH NO. **I-3**

JOB NO.: 17G218-2 PROJECT: Proposed Commercial/Industrial Building

LOCATION: San Bernardino County, CA

DATE: 3-20-2018

EQUIPMENT USED: Backhoe

LOGGED BY: Scott McCann


ORIENTATION: N 6 E

TOP OF TRENCH ELEVATION: 1205.5 feet msl

WATER DEPTH: Dry

SEEPAGE DEPTH: Dry

READINGS TAKEN: At Completion



KEY TO SAMPLE TYPES: B - BULK SAMPLE (DISTURBED) R - RING SAMPLE 2-1/2" DIAMETER

TRENCH NO. 1-4

JOB NO.: 17G218-2

PROJECT: Proposed Commercial/Industrial Building

LOCATION: San Bernardino County, CA

DATE: 3-20-2018

EQUIPMENT USED: Backhoe

LOGGED BY: Scott McCann


ORIENTATION: N 89 W

TOP OF TRENCH ELEVATION: 1199 feet msl

WATER DEPTH: Dry

SEEPAGE DEPTH: Dry

READINGS TAKEN: At Completion



KEY TO SAMPLE TYPES: B - BULK SAMPLE (DISTURBED) R - RING SAMPLE 2-1/2" DIAMETER (RELATIVELY UNDISTURBED)

TRENCH NO. **I-5**

JOB NO.: 17G218-2

EQUIPMENT USED: Backhoe

WATER DEPTH: Dry

PROJECT: Proposed Commercial/Industrial Building

LOGGED BY: Scott McCann

SEEPAGE DEPTH: Dry

LOCATION: San Bernardino County, CA

ORIENTATION: S 86 W

READINGS TAKEN: At Completion DATE: 3-20-2018 TOP OF TRENCH ELEVATION: 1201 feet msl DRY DENSITY (PCF) MOISTURE (%) SAMPLE DEPTH **EARTH MATERIALS GRAPHIC REPRESENTATION DESCRIPTION** S 86 W SCALE: 1" = 5' A: ALLUVIUM: Gray Brown Silty fine Sand to fine Sandy Silt, little medium Sand, trace coarse Sand, abundant fine root fibers, loose - moist B: ALLUVIUM: Light Gray Brown Silty fine Sand, little medium Sand, trace fine root fibers, medium dense - dry to damp b Trench Terminated @ 4 feet Bottom of Trench Elevation: 1197 feet msl 10

KEY TO SAMPLE TYPES: B - BULK SAMPLE (DISTURBED) R - RING SAMPLE 2-1/2" DIAMETER

Project Name Project Location Project Number Engineer Proposed Commercial/Industrial Building
San Bernardino County, CA
17G218-2
Scott McCann

Infiltration Test No

I-1

<u>Constants</u>									
	Diameter	Area	Area						
	(ft)	(ft ²)	(cm ²)						
Inner	1	0.79	730						
Anlr. Spac	2	2.36	2189						

					Flow	Readings	<u> </u>		<u>Infiltrati</u>	on Rates	
			Interval	Inner	Ring	Annula	Space	Inner	Annular	Inner	Annular
Test			Elapsed	Ring	Flow	r Ring	Flow	Ring*	Space*	Ring*	Space*
Interval		Time (hr)	(min)	(ml)	(cm ³)	(ml)	(cm ³)	(cm/hr)	(cm/hr)	(in/hr)	(in/hr)
1	Initial	10:45 AM	10	250	1750	1000	5450	1/ 20	14.94	F 67	5.88
1	Final	10:55 AM	10	2000	1/50	6450	3430	14.39	14.94	5.67	5.00
2	Initial	10:56 AM	10	300	1400	200	4500	11.51	12.33	4.53	4.86
2	Final	11:06 AM	21	1700	1400	4700	4300	11.51	12.55	4.55	4.00
3	Initial	11:07 AM	10	50	1250	0	4150	10.28	11.38	4.05	4.48
3	Final	11:17 AM	32	1300	1230	4150	4130	10.20	11.50	4.05	4.40
4	Initial	11:18 AM	10	50	1175	600	3900	9.66	10.69	3.80	4.21
4	Final	11:28 AM	43	1225	11/3	4500	3900	9.00	10.09	3.60	4.21
5	Initial	11:29 AM		150	1125	500	3900	9.25	10.69	3.64	4.21
J	Final	11:39 AM	54	1275	1123	4400	3900	9.23	10.09	3.04	7.21
6	Initial	11:40 AM	10	200	1150	350	3850	9.46	10.55	3.72	4.15
O	Final	11:50 AM	65	1350	1130	4200	3030	9.40	10.55	3.72	4.13
7	Initial	11:51 AM	10	0	1125	200		9.25	10.55	3.64	4.15
	Final	12:01 PM	75	1125	1123	4050	3030	9.23	10.55	5.04	7.13

Project Name Project Location Project Number Engineer Proposed Commercial/Industrial Building
San Bernardino County, CA
17G218-2
Scott McCann

Infiltration Test No

I-2

<u>Constants</u>									
	Diameter	Area	Area						
	(ft)	(ft ²)	(cm ²)						
Inner	1	0.79	730						
Anlr. Spac	2	2.36	2189						

					Flow	Readings	<u>S</u>		<u>Infiltrati</u>	on Rates	
			Interval	Inner	Ring	Annula	Space	Inner	Annular	Inner	Annular
Test			Elapsed	Ring	Flow	r Ring	Flow	Ring*	Space*	Ring*	Space*
Interval		Time (hr)	(min)	(ml)	(cm ³)	(ml)	(cm ³)	(cm/hr)	(cm/hr)	(in/hr)	(in/hr)
1	Initial	9:15 AM	10	300	1500	900	4600	12.33	12.61	4.86	4.96
1	Final	9:25 AM	10	1800	1300	5500	4000	12.33	12.01	4.00	4.90
2	Initial	9:26 AM	10	200	1175	600	4250	9.66	11.65	3.80	4.59
	Final	9:36 AM	21	1375	11/5	4850	4230	9.00	11.05	5.00	4.39
3	Initial	9:37 AM	10	0	1075	250	4100	8.84	11.24	3.48	4.42
3	Final	9:47 AM	32	1075	10/3	4350	4100	0.04	11.24	3.46	4.42
4	Initial	9:48 AM	10	50	1000	100	3950	8.22	10.83	3.24	4.26
4	Final	9:58 AM	43	1050	1000	4050	3930	0.22	10.65	3.24	4.20
5	Initial	9:59 AM	10	350	950	50	3850	7.81	10.55	3.08	4.15
J	Final	10:09 AM	54	1300	930	3900	3030	7.01	10.55	3.00	4.13
6	Initial	10:10 AM	10	250	925	500	3850	7.61	10.55	2.99	4.15
U	Final	10:20 AM	65	1175	923	4350	3030	7.01	10.55	2.99	4.13
7	Initial	10:21 AM	10	200	950	350	3850	7.81	10.55	3.08	4.15
	Final	10:31 AM	75	1150	930	4200	3630	7.01	10.33	3.06	4.13

Project Name Project Location Project Number Engineer Proposed Commercial/Industrial Building
San Bernardino County, CA
17G218-2
Scott McCann

Infiltration Test No

I-3

<u>Constants</u>									
	Diameter	Area	Area						
	(ft)	(ft ²)	(cm ²)						
Inner	1	0.79	730						
Anlr. Spac	2	2.36	2189						

					Flow I	Readings	<u> </u>		<u>Infiltrati</u>	on Rates	
			Interval	Inner	Ring	Annula	Space	Inner	Annular	Inner	Annular
Test			Elapsed	Ring	Flow	r Ring	Flow	Ring*	Space*	Ring*	Space*
Interval		Time (hr)	(min)	(ml)	(cm ³)	(ml)	(cm ³)	(cm/hr)	(cm/hr)	(in/hr)	(in/hr)
1	Initial	7:45 AM	10	450	1450	600	5400	11 02	14.80	4.69	5.83
1	Final	7:55 AM	10	1900	1450	6000	3400	11.92	14.80	4.69	5.65
2	Initial	7:56 AM	10	0	1225	200	4950	10.07	13.57	3.97	5.34
2	Final	8:06 AM	21	1225	1223	5150	4950	10.07	13.37	3.97	5.54
3	Initial	8:07 AM	10	200	1175	250	4700	9.66	12.88	3.80	5.07
3	Final	8:17 AM	32	1375	11/3	4950	4700	9.00	12.00	3.60	3.07
4	Initial	8:18 AM	10	100	1050	350	4550	8.63	12.47	3.40	4.91
4	Final	8:28 AM	43	1150	1030	4900	4550	0.05	12.47	3.40	4.51
5	Initial	8:29 AM	10	150	1025	900	4450	8.43	12.20	3.32	4.80
J	Final	8:39 AM	54	1175	1023	5350	4430	0.43	12.20	3.32	4.00
6	Initial	8:40 AM	10	150	1025	1100	4400	8.43	12.06	3.32	4.75
O	Final	8:50 AM	65	1175	1023	5500	4400	0.43	12.00	3.32	4.73
7	Initial	8:51 AM	10	300	1000	400	4 /I < I II I	8.22	11.79	3.24	4.64
	Final	9:01 AM	75	1300	1000	4700	4300	0.22	11./9	5.24	4.04

Project Name Project Location Project Number Engineer Proposed Commercial/Industrial Building
San Bernardino County, CA
17G218-2
Scott McCann

Infiltration Test No

I-4

<u>Constants</u>									
	Diameter	Area	Area						
	(ft)	(ft ²)	(cm ²)						
Inner	1	0.79	730						
Anlr. Spac	2	2.36	2189						

					Flow I	Readings	<u> </u>		<u>Infiltrati</u>	on Rates	
			Interval	Inner	Ring	Annula	Space	Inner	Annular	Inner	Annular
Test			Elapsed	Ring	Flow	r Ring	Flow	Ring*	Space*	Ring*	Space*
Interval		Time (hr)	(min)	(ml)	(cm ³)	(ml)	(cm ³)	(cm/hr)	(cm/hr)	(in/hr)	(in/hr)
1	Initial	12:30 PM	10	250	1600	700	4850	13.16	13.29	5.18	5.23
1	Final	12:40 PM	10	1850	1000	5550	4630	13.10	13.29	5.16	3.23
2	Initial	12:41 PM	10	0	1325	800	3900	10.90	10.69	4.29	4.21
	Final	12:51 PM	21	1325	1323	4700	3900	10.90	10.09	4.29	4.21
3	Initial	12:52 PM	10	0	1225	450	3850	10.07	10.55	3.97	4.15
3	Final	1:02 PM	32	1225	1225	4300	3030	10.07	10.55	3.97	4.13
4	Initial	1:03 PM	10	0	1175	300	3900	9.66	10.69	3.80	4.21
4	Final	1:13 PM	43	1175	11/5	4200	3900	9.00	10.09	3.00	4.21
5	Initial	1:14 PM	10	125	1175	650	3750	9.66	10.28	3.80	4.05
3	Final	1:24 PM	54	1300	11/3	4400	3/30	9.00	10.20	3.60	4.03
6	Initial	1:25 PM	10	1350	1150	4300	3650	9.46	10.01	3.72	3.94
U	Final	1:35 PM	65	2500	1130	7950	3030	3.40	10.01	3.72	3.54
7	Initial	1:36 PM	10	2550	1150	8150		9.46	9.87	3.72	3.89
	Final	1:46 PM	75	3700	1130	11750	3000	5.40	5.07	3.72	3.09


Project Name Project Location Project Number Engineer Proposed Commercial/Industrial Building
San Bernardino County, CA
17G218-2
Scott McCann

Infiltration Test No

I-5

<u>Constants</u>									
	Diameter	Area	Area						
	(ft)	(ft ²)	(cm ²)						
Inner	1	0.79	730						
Anlr. Spac	2	2.36	2189						

				Flow Readings			<u>Infiltration Rates</u>				
			Interval	Inner	Ring	Annula	Space	Inner	Annular	Inner	Annular
Test			Elapsed	Ring	Flow	r Ring	Flow	Ring*	Space*	Ring*	Space*
Interval		Time (hr)	(min)	(ml)	(cm ³)	(ml)	(cm ³)	(cm/hr)	(cm/hr)	(in/hr)	(in/hr)
1	Initial	2:10 PM	10	250	1400	900	441111	11.51	12.06	4.53	4.75
	Final	2:20 PM	10	1650		5300					
2	Initial	2:21 PM	10	50	950	100	1 3250	7.81	10.55	3.08	4.15
	Final	2:31 PM	21	1000		3950					
3	Initial	2:32 PM	10	50	825	300	3700	6.78	10.14	2.67	3.99
	Final	2:42 PM	32	875		4000					
4	Initial	2:43 PM	10	900	825	4100	1 4450	6.78	9.18	2.67	3.62
	Final	2:53 PM	43	1725		7450					
5	Initial	2:54 PM	10	50	800	300	1 5550	6.58	9.18	2.59	3.62
	Final	3:04 PM	54	850		3650					
6	Initial	3:05 PM	10	900	800	3900	4 3/411111	6.58	9.32	2.59	3.67
	Final	3:15 PM	65	1700		7300					
7	Initial	3:16 PM	10	1725	//5	7450	. < < 511	6.37	9.18	2.51	3.62
	Final	3:26 PM	75	2500		10800					




Sample Description	I-1 @ 4 feet
Soil Classification	Light Gray Brown Silty fine Sand

Proposed Commercial/Industrial Building

San Bernardino County, CA Project No. 17G218-2

PLATE C-1






Sample Description	I-2 @ 6 feet
Soil Classification	Light Gray Brown Silty fine Sand, trace medium Sand

Proposed Commercial/Industrial Building San Bernardino County, CA

Project No. 17G218-2

PLATE C-2






Sample Description	I-3 @ 7 feet
Soil Classification	Light Gray Brown Silty fine Sand

Proposed Commercial/Industrial Building San Bernardino County, CA

Project No. 17G218-2

Project No. 17G218






Sample Description	I-4 @ 4 feet
Soil Classification	Light Gray Brown Silty fine Sand

Proposed Commercial/Industrial Building San Bernardino County, CA

Project No. 17G218-2

PLATE C-4





Sample Description	I-5 @ 4 feet
Soil Classification	Light Gray Brown Silty fine Sand, little medium Sand

Proposed Commercial/Industrial Building
San Bernardino County, CA

Project No. 17G218-2

PLATE C-5

