

STREET IMPROVEMENT GENERAL NOTES

1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THIS PLAN AND THE SAN BERNARDINO COUNTY STANDARDS AND SPECIFICATIONS.
2. BENCH MARK DATA:
ELEVATION: 0000.00
3. STREET MARKERS PER SAN BERNARDINO COUNTY STANDARD NO. 303, 304A AND 303B SHALL BE CONSTRUCTED AT EACH INTERSECTION.
4. STREET MARKERS SHALL BE CONSTRUCTED AT EACH INTERSECTION IN ACCORDANCE WITH APPLICABLE SAN BERNARDINO COUNTY STANDARDS. ALL SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH COUNTY AND STATE SPECIFICATIONS.
5. A PERMIT WILL BE REQUIRED FROM THE COUNTY OF SAN BERNARDINO DEPARTMENT OF PUBLIC WORKS PRIOR TO ANY ENCROACHMENT OR CONSTRUCTION WITHIN THE COUNTY OF SAN BERNARDINO EASEMENT OR RIGHTS-OF-WAY.
6. LEAVE 8' x 8' BLOCKOUTS IN SIDEWALKS FOR MAILBOXES, ETC. WHEN SIDEWALK IS PLACED ADJACENT TO CURB.
7. IF ASPHALT CONCRETE IS TO BE PLACED DIRECTLY ON SUBGRADE OF ROAD OR DRAINAGE FACILITIES, A SOIL STERILANT REGISTERED BY THE EPA FOR USE UNDER C.I. AND P.C. SHALL BE UNIFORMLY APPLIED AT THE MANUFACTURER'S RECOMMENDED RATE FOR THE FULL PAVEMENT WIDTH PRIOR TO PAVING.
8. AT COMPLETION OF ROUGH GRADING, A MATERIALS REPORT AND THE PROPOSED STRUCTURAL SECTIONS SHALL BE SUBMITTED TO THE ENGINEER OF THE SAN BERNARDINO COUNTY DEPARTMENT OF PUBLIC WORKS, TRANSPORTATION OPERATIONS DIVISION, 1001 N. G STREET, SUITE 200, SAN BERNARDINO, CALIFORNIA 92410. THE REPORT SHALL INCLUDE THE FOLLOWING: A. A TABULATED PLAT SHOWING THE LOCATION OF THE SAMPLING, A TABULATION OF SIEVE ANALYSIS AND SAND EQUIVALENT TEST RESULTS, A STATEMENT OF RECOMMENDED STRUCTURAL SECTION AND TEST DATA SHEETS FOR ALL R-VALUE TESTS PERFORMED, INCLUDING EXPANSION PRESSURE READINGS. APPROVAL WILL BE GIVEN WHEN ALL STRUCTURAL SECTION REQUIREMENTS HAVE BEEN MET.
9. COMPACTION TESTS OF EMBANKMENT CONSTRUCTION, TRENCH BACKFILL, COMPACTING ORIGINAL GROUND, ALL SUBGRADES SHALL BE PERFORMED AT NO COST TO SAN BERNARDINO COUNTY. A WRITTEN REPORT WITH THESE COMPACTION TESTS SHALL BE SUBMITTED TO THE SAN BERNARDINO COUNTY DEPARTMENT OF PUBLIC WORKS, TRANSPORTATION OPERATIONS DIVISION, PERMIT SECTION FOR APPROVAL PRIOR TO PLACEMENT OF BASE MATERIALS AND/OR SURFCING.
10. AT THE COMPLETION OF PAVING A MATERIALS REPORT SHALL BE SUBMITTED TO THE SAN BERNARDINO COUNTY PUBLIC WORKS DEPARTMENT, TRANSPORTATION OPERATIONS DIVISION, PERMIT SECTION, LISTING ALL TESTS OR DETERMINATIONS COMPLETED TO VERIFY:

A. R-VALUE, SIEVE ANALYSIS AND SAND EQUIVALENT OF AGGREGATE BASES
B. STABILITY, OIL CONTENT AND SIEVE ANALYSIS OF ASPHALT SURFCING

11. THE WATER MAINS AND THE GAS MAINS SHALL BE PLACED UNDERGROUND PRIOR TO PAVING CONSTRUCTION. THE SERVICE LATERALS FOR THE WATER SYSTEM SHALL BE INSTALLED AT A LATER DATE, WHERE IT IS NECESSARY TO CROSS PAVEMENT. SERVICE LATERALS SHALL BE BORED IN TO PLACE.
12. FILL AND GRADE TO DRAIN ALL LOW AREAS ABUTTING TRACT ROADS TO A MINIMUM OF 1% GRADES.
13. ALL LATERAL CUTS INTO COUNTY MAINTAINED ROADWAYS SHALL BE TESTED TO VERIFY DENSIFICATION TO 90% RELATIVE COMPACTION (R.C.) AT VARYING DEPTHS TO WITHIN 0.5' OF GRADING PLANE. THE TOP 0.5' SHALL BE DENSIFIED TO 92%.
14. ALL LONGITUDINAL CUTS SHALL BE TESTED IN ACCORDANCE WITH THE SPECIFIED LIMITS AND FREQUENCY AS OUTLINED IN SECTION 6 OF THE SAN BERNARDINO COUNTY STANDARDS AND SPECIFICATIONS.
15. IMMEDIATELY FOLLOWING REMOVAL OF EXISTING PAVEMENT OR DIKE OR CURB AND/OR GUTTER, THE CONTRACTOR SHALL DILIGENTLY PURSUE THIS PORTION OF WORK UNTIL COMPLETION.
16. DEPARTMENT OF PUBLIC WORKS APPROVAL DOES NOT INCLUDE WATER SEWER SYSTEM OR ESTIMATE OF QUANTITIES.
17. A PERMIT SHALL BE OBTAINED FROM THE SAN BERNARDINO COUNTY DEPARTMENT OF PUBLIC WORKS PRIOR TO ANY CONSTRUCTION ON THIS PROJECT, THAT FALLS WITHIN SAN BERNARDINO COUNTY, ROAD RIGHT-OF-WAY.
18. EXPANSIVE SOILS, IN EXPANSIVE SOIL AREAS, THE SUBGRADE UNDER CURBS, GUTTERS, SIDEWALK AND DRIVEWAY APPROACHES SHALL BE SCARIFIED TO THE DEPTH OF AT LEAST EIGHT (8) INCHES AND MOISTURE SHALL BE APPLIED TO MAINTAIN FREE WATER WITHOUT COMPACTION EFFORTS.
19. CURB & GUTTER, GROSS GUTTER AND SPANDRELS SHALL BE SO CONSTRUCTED THAT A MINIMUM OF PONDING OCCURS. SECTIONS ACCEPTANCE. SECTIONS WHICH HAVE WATER PONDING MORE THAN 62" WIDE OR MORE THAN 4" LONG SHALL BE SAW-CUT AND REMOVED IN LENGTHS NOT LESS THAN 4' AND REPLACED TO REDUCE PONDING TO THE MAXIMUM SPECIFIED.
20. IF DURING CONSTRUCTION, GROUND WATER IS ENCOUNTERED, A SYSTEM APPROVED BY THE SAN BERNARDINO COUNTY DEPARTMENT OF PUBLIC WORKS SHALL NOT BE ENTERED INTO THE COUNTY MAINTAINED ROAD SYSTEM.
21. THIS PRIVATE ROAD SHALL NOT BE ENTERED INTO THE COUNTY MAINTAINED ROAD SYSTEM.
22. THE ENGINEER SHALL INSPECT AND CERTIFY THAT ALL PRIVATE ROAD AND DRAINAGE IMPROVEMENTS HAVE BEEN BUILT IN ACCORDANCE WITH THE APPROVED PLANS.
23. ALL 0.40% OR LESS CURB GRADE LINES SHALL BE STAGED AT 25' INTERVALS AND FORMS CERTIFIED BY THE ENGINEER BEFORE POURING CONCRETE.
24. EXISTING COUNT ROADS THAT WILL REQUIRE RECONSTRUCTION SHALL REMAIN OPEN FOR TRAFFIC AT ALL TIMES WITH ADEQUATE DETOURS DURING ACTUAL CONSTRUCTION.
25. THE PRIVATE ENGINEER IS RESPONSIBLE FOR ASSURING THE ACCURACY AND ACCEPTABILITY OF WORK HEREON. IN THE EVENT OF DISCREPANCIES ARISING DURING CONSTRUCTION, THE PRIVATE ENGINEER SHALL BE RESPONSIBLE FOR DETERMINING AN ACCEPTABLE SOLUTION AND REVISE THE PLAN FOR APPROVAL BY THE COUNTY OF SAN BERNARDINO.
26. SHOULD ANY EXISTING STOP SIGN BE LOCATED ON A DEVELOPED CORNER OF AN INTERSECTION, IT MUST BE MAINTAINED IN PLACE NEXT TO THE EXISTING PAVEMENT UNTIL SUCH TIME AS THE WIDENED ROADWAY IS OPEN FOR TRAFFIC. AT THAT TIME, IT WILL BE RELOCATED THREE (3) FEET BEHIND THE NEW CURB IN THE VICINITY OF THE BEGINNING OF THE CURB RETURN OR AS OTHERWISE DIRECTED BY THE ENGINEER.

TRAFFIC CONTROL – GENERAL NOTES

1. ALL SIGNING, STRIPING AND PAVEMENT MARKINGS SHALL BE IN CONFORMANCE WITH THE MUTCD 2003 AND THE CALIFORNIA SUPPLEMENT TO THE MUTCD 2003.
2. ALL STRIPING (LONG LINE) AND PAVEMENT MARKINGS SHALL BE RETROREFLECTIVE PAINT.
3. ALL SIGNS SHALL BE OF HIGH INTENSITY (FHWA TYPE II/IV) RETROREFLECTIVE SHEETING. STOP SIGNS SHALL BE (FHWA TYPE VI) RETROREFLECTIVE SHEETING. ALL OTHER SIGNS SHALL BE (FHWA TYPE I) RETROREFLECTIVE SHEETING. ALL SCHOOL SIGNS SHALL BE DIAMOND GRADE (FHWA TYPE X) FLUORESCENT YELLOW-GREEN (FYG) RETROREFLECTIVE SHEETING.
4. ALL DELINEATORS AND CHANNELIZERS SHALL BE OF (FHWA TYPE VI) RETROREFLECTIVE SHEETING.
5. SIGNS SHALL BE MOUNTED ON METAL POSTS SIMILAR TO COUNTY STANDARDS 303 (a) AND 303 (b).
6. ALL CONFLICTING STRIPING AND PAVEMENT MARKINGS NOT SHOWN ON PLANS SHALL BE REMOVED OR AS DIRECTED BY THE COUNTY REPRESENTATIVE.
7. ALL CONFLICTING SIGNS SHALL BE REMOVED, RELOCATED OR COVERED BY THE CONTRACTOR. RELOCATABLE SIGNS SHALL BE INSTALLED AS SPECIFIED ON THE PLANS OR AS DIRECTED BY THE COUNTY REPRESENTATIVE.
8. ALL EXISTING SIGNING, STRIPING AND PAVEMENT MARKINGS (i.e. GROSS STREET STOP, STOP LIMIT LINE AND CROSSWALK PAVEMENT MARKINGS) NOT SHOWN ON PLANS, IF REMOVED/OBLITERATED, SHALL BE REPLACED/RESTORED OF SAME KIND AND IN CONFORMANCE WITH CURRENT EDITION OF THE MUTCD 2003 AND THE CALIFORNIA SUPPLEMENT TO THE MUTCD 2003.
9. THE CONTRACTOR SHALL NOTIFY COUNTY REPRESENTATIVE TO SCHEDULE A FINAL REVIEW WALK THROUGH) WITH TRAFFIC DIVISION PERSONNEL FOR APPROVAL OF TRAFFIC CONTROL DEVICES PRIOR TO PROJECT ACCEPTANCE.

Underground Service Alert



Call: TOLL FREE
1-800-227-2600

TWO WORKING DAYS BEFORE YOU DIG

BENCHMARK

xxxxxxxxxxxxxxxxxxxx

PREPARED BY:

STREET IMPROVEMENT PLAN

CONSTRUCTION NOTES

- ① CONSTRUCT " AC OVER " C.A.B. (CLASS I) PER GENERAL NOTE 8.

QUANTITY

XXXXXXX

INDEX MAP

SCALE 1"= XX'

LEGEND

xxxxxxxxxxxxxxxxxxxx

SHEET INDEX

- SHEET 1: TITLE SHEET
- SHEET 2:
- SHEET 3:

PRIVATE ENGINEER'S NOTE TO CONTRACTOR

THE EXISTANCE AND LOCATION OF ANY UNDERGROUND UTILITY PIPES, CONDUITS, OR STRUCTURES SHOWN ON THESE PLANS ARE OBTAINED BY A SEARCH OF THE AVAILABLE RECORDS. TO THE BEST OF OUR KNOWLEDGE THERE ARE NO EXISTING UTILITIES EXCEPT AS SHOWN ON THESE PLANS. THE CONTRACTOR IS REQUIRED TO TAKE THE DUE PRECAUTIONARY MEASURES TO PROTECT THE UTILITIES SHOWN ON THESE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE UTILITY PIPES, CONDUITS OR STRUCTURES SHOWN ON THESE DRAWINGS.

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR OBTAINING ALL NECESSARY PERMITS AND CONDUCTING ALL WORK IN ACCORDANCE WITH ALL APPLICABLE ORDINANCES, RULES AND REGULATIONS, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS, AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE COUNTY OF SAN BERNARDINO, THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, INCLUDING ATTORNEY'S FEES, DAMAGES AND COSTS OF THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.

VICINITY MAP

MARK	REVISIONS	APPROVAL DATE	COUNTY OF SAN BERNARDINO DEPARTMENT OF PUBLIC WORKS		TITLE SHEET	
			JACOB BARBO CHIEF, TRAFFIC DIVISION	DATE	APPROVED BY:	ROAD NO.
						TRACT NO. XXXXX
						CITY
						SHEET 1 OF X